

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

49 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
1	1	LS	CLEARING & GRUBBING FOR: _____ DOLLARS CENTS			
1 M/F	1	LS	MOBILIZATION WITH FIELD OFFICE FOR: _____ DOLLARS CENTS			
1S	EA	3	JOB INFORMATION SIGN FOR: _____ DOLLARS CENTS			
2X	3,300	CY	UNCLASSIFIED EXCAVATION FOR: _____ DOLLARS CENTS			
3	1,000	CY	TRENCH CULVERT AND BRIDGE EXCAVATION FOR: _____ DOLLARS CENTS			
4A	100	SY	CEMENT CONCRETE BREAKING (PAVEMENT) FOR: _____ DOLLARS CENTS			
4B	5	CY	CEMENT CONCRETE BREAKING (STRUCTURES) FOR: _____ DOLLARS CENTS			
5C	250	CY	SELECTED FILL FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

51 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
5D	55	CY	SELECTED GRANULAR FILL FOR: _____ DOLLARS CENTS			
7	8,000	SY	PREPARING FINE GRADE FOR: _____ DOLLARS CENTS			
8	1	LS	TRIMMING SHOULDERS AND SLOPES FOR: _____ DOLLARS CENTS			
9	550	CY	TOPSOIL FOR: _____ DOLLARS CENTS			
10A-1	620	SF	EXCAVATION PROTECTION SYSTEM FOR: _____ DOLLARS CENTS			
12G	25	LF	RELAYING PIPE FOR: _____ DOLLARS CENTS			
12H	120	LF	CLEANING EXISTING DRAINAGE SYSTEM FOR: _____ DOLLARS CENTS			
12P-15	1,120	LF	15" DIAMETER SMOOTH INTERIOR CORRUGATED POLYETHYLENE DRAIN PIPE FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
QUAKER MEETING HOUSE ROUNDABOUT  
ITEMIZED PROPOSAL  
FEBRUARY 2024**

Nassau County DPW

53 of 354

Contract no. T62801-01G  
Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
12P-18	180	LF	18" DIAMETER SMOOTH INTERIOR CORRUGATED POLYETHYLENE DRAIN PIPE FOR: _____ DOLLARS CENTS			
13A	75	CY	CATCH BASIN FOR: _____ DOLLARS CENTS			
13BP-4	6	VF	PRECAST MANHOLE 4' DIAMETER FOR: _____ DOLLARS CENTS			
14	1	EA	CONNECTIONS TO EXISTING DRAINAGE FACILITIES FOR: _____ DOLLARS CENTS			
16B	2	EA	ALTERING BRICK MANHOLES (TOP SLAB) WITH FRAME HEAD FOR: _____ DOLLARS CENTS			
16SS-1	4	EA	CHANGE ELEVATIONS OF SANITARY SEWER MANHOLES (MINOR ADJUSTMENT) FOR: _____ DOLLARS CENTS			
16SS-2	2	EA	CHANGE ELEVATIONS OF SANITARY SEWER MANHOLES (MAJOR ADJUSTMENT) FOR: _____ DOLLARS CENTS			
22C-2	3,450	TONS	BASE COURSE ASPHALT CONCRETE TYPE DENSE BASE FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

55 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
24	20	CY	CEMENT CONCRETE PAVEMENT FOR: _____ DOLLARS CENTS			
26C	2,660	LF	CONCRETE CURB TYPE C FOR: _____ DOLLARS CENTS			
26CG	400	LF	COMBINATION CONCRETE CURB & GUTTER FOR: _____ DOLLARS CENTS			
26D	820	LF	CONCRETE CURB TYPE D MOUNTABLE FOR: _____ DOLLARS CENTS			
26F	360	LF	CONCRETE CURB TYPE F FLUSH FOR: _____ DOLLARS CENTS			
26T	450	LF	CONCRETE CURB TYPE T TRAVERSABLE FOR: _____ DOLLARS CENTS			
27	2,475	SF	CEMENT CONCRETE SIDEWALK FOR: _____ DOLLARS CENTS			
27DW	10	SF	DETECTABLE WARNING SURFACE FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

57 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
28	210	SF	CEMENT CONCRETE DRIVEWAY & DRIVEWAY APRONS FOR: _____ DOLLARS CENTS			
29	950	SF	DRIVEWAY RESTORATION FOR: _____ DOLLARS CENTS			
30	1,400	SY	METAL REINFORCEMENT FOR CONCRETE PAVEMENT FOR: _____ DOLLARS CENTS			
34	28,880	LBS	MISCELLANEOUS METALS FOR: _____ DOLLARS CENTS			
35	200	LF	RESETTING GUIDE RAILING FOR: _____ DOLLARS CENTS			
36D	850	TONS	ASPHALT CONCRETE TYPE 3 BINDER FOR: _____ DOLLARS CENTS			
36DRAN	700	TONS	RUT AVOIDANCE ASPHALT CONCRETE TYPE 1A (TOP RA NEW CONSTRUCTION) FOR: _____ DOLLARS CENTS			
36T	450	TONS	TEMPORARY PAVEMENT FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

59 of 354

Quaker Meeting House Road Roundabout Construction  
 Contract no. T62801-01G

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
39-4	210	SF	PAVING STONES ON A 4" AGGREGATE BASE FOR: _____ DOLLARS CENTS			
40R	110	SF	RESET EXISTING STONE BLOCK PAVEMENT FOR: _____ DOLLARS CENTS			
58A	70	LF	SAWCUTTING EXISTING NON-ROADWAY ASHPALT FOR: _____ DOLLARS CENTS			
58RPC	250	LF	SAWCUTTING EXISTING ROADWAY PAVEMENT AND CONCRETE FOR: _____ DOLLARS CENTS			
60	1	EA	ALTER WATER SERVICE CONNECTIONS FOR: _____ DOLLARS CENTS			
61H	1	EA	RELOCATIONS OF FIRE HYDRANTS FOR: _____ DOLLARS CENTS			
61S	110	LF	RELOCATIONS OF WATER MAINS COMPLETE FOR: _____ DOLLARS CENTS			
62	1	EA	RELOCATE BURIED ELECTRICAL SERVICE CONNECTION FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

61 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
64	50	LF	RESET EXISTING FENCE FOR: _____ DOLLARS CENTS			
99-10X	20	VF	PRECAST CONCRETE LEACHING BASIN (10' DIAMETER) FOR: _____ DOLLARS CENTS			
100-10	320	VF	PRECAST CONCRETE DIFFUSION WELL (10' DIAMETER) FOR: _____ DOLLARS CENTS			
102	1	LS	WORK ZONE TRAFFIC CONTROL FOR: _____ DOLLARS CENTS			
102D	1,100	DAYS	FLASHING ARROW BOARD FOR: _____ DOLLARS CENTS			
102PVMS	1,230	DAYS	PORTABLE MESSAGE SIGN FOR: _____ DOLLARS CENTS			
104XF	100	LF	REMOVE EXISTING FENCE FOR: _____ DOLLARS CENTS			
110	4	CF	MASONRY PIPE PLUGS FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

63 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
114	12	EA	ADJUSTMENT OF WATER VALVE BOX ELEVATION FOR: _____ DOLLARS CENTS			
117	2,000	LF	TEMPORARY FENCE/TREE GUARDS FOR: _____ DOLLARS CENTS			
120	6	EA	RELOCATION AND REATTACHMENT OF EXISTING LIGHTING UNITS FOR: _____ DOLLARS CENTS			
121	5	CY	DRYBOUND BASE COURSE FOR: _____ DOLLARS CENTS			
122	35	EA	TEST HOLES FOR: _____ DOLLARS CENTS			
126A	60	LF	NEW STONE BLOCK CURB FOR: _____ DOLLARS CENTS			
126B	30	LF	RESET EXISTING STONE BLOCK CURB FOR: _____ DOLLARS CENTS			
126C	60	LF	RESET EXISTING BRICK CURB FOR: _____ DOLLARS CENTS			



**PROJECT NO. T62801-01  
QUAKER MEETING HOUSE ROUNDABOUT  
ITEMIZED PROPOSAL  
FEBRUARY 2024**

Nassau County DPW

65 of 354

Quaker Meeting House Road Roundabout Construction  
Contract no. T62801-01G

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
127	1	EA	RELOCATING EXISTING HYDRANT FOR: _____ DOLLARS CENTS			
132	1	EA	PLOWABLE RAISED REFLECTORIZED PAVEMENT MARKERS FOR: _____ DOLLARS CENTS			
136	1	LS	SURVEY STAKEOUT FOR: _____ DOLLARS CENTS			
137	6,700	LF	REMOVE EXISTING TRAFFIC MARKINGS FOR: _____ DOLLARS CENTS			
141	2,100	LF	SILT FENCE FOR: _____ DOLLARS CENTS			
178W	4,360	LF	PAVEMENT MARKINGS, PAINTINGS & STRIPING (WHITE) FOR: _____ DOLLARS CENTS			
178Y	6,700	LF	PAVEMENT MARKINGS, PAINTINGS & STRIPING (YELLOW) FOR: _____ DOLLARS CENTS			
185A	160	LF	RELOCATE RESIDENTIAL SPRINKLER SYSTEMS FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

67 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES						
	QUANTITY	UNIT					
199	1	LS	INTERIM PAYMENTS - FIXED FOR: _____ DOLLARS CENTS	\$150,000	00	\$150,000	00
199A*	1	LS	ASPHALT PRICE ADJUSTMENT FOR: _____ DOLLARS CENTS	\$10,000	00	\$10,000	00
361A	3	EA	PLANTING TREES AND SHRUBS - A FOR: _____ DOLLARS CENTS				
361B	30	EA	PLANTING TREES AND SHRUBS - B FOR: _____ DOLLARS CENTS				
361C	220	EA	PLANTING TREES AND SHRUBS - C FOR: _____ DOLLARS CENTS				
361D	1	EA	PLANTING TREES AND SHRUBS - D FOR: _____ DOLLARS CENTS				
361E	340	EA	PLANTING TREES AND SHRUBS - E FOR: _____ DOLLARS CENTS				
361F	880	EA	FURNISH AND INSTALL FLOWERING PLUGS FOR: _____ DOLLARS CENTS				

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

69 of 354

Quaker Meeting House Road Roundabout Construction  
 Contract no. T62801-01G

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
362	130	CY	TRIPLE SHREDEDDED MULCH FOR: _____ DOLLARS CENTS			
365	3,570	SF	SODDING FOR: _____ DOLLARS CENTS			
367	0.75	AC	HYDROSEEDING FOR: _____ DOLLARS CENTS			
372BX	12	EA	TREE & STUMP REMOVAL 6" < 12" FOR: _____ DOLLARS CENTS			
372CX	30	EA	TREE & STUMP REMOVAL 12" < 24" FOR: _____ DOLLARS CENTS			
372DX	5	EA	TREE & STUMP REMOVAL 24" < 36" FOR: _____ DOLLARS CENTS			
372EX	2	EA	TREE & STUMP REMOVAL 36" < 48" FOR: _____ DOLLARS CENTS			
372FX	3	EA	TREE & STUMP REMOVAL 48" AND UP FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

71 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
442W	5,670	LF	WHITE EPOXY REFLECTORIZED PAVEMENT STRIPES FOR: _____ DOLLARS CENTS			
442A	15	EA	EPOXY REFLECTORIZED PAVEMENT MARKINGS - ARROWS FOR: _____ DOLLARS CENTS			
442C	50	EA	EPOXY REFLECTORIZED PAVEMENT MARKINGS - CHARACTER FOR: _____ DOLLARS CENTS			
442Y	5,470	LF	YELLOW EPOXY REFLECTORIZED PAVEMENT STRIPES FOR: _____ DOLLARS CENTS			
500	1	EA	REMOVAL AND RELOCATION OF STREET LIGHT & POLE FOR: _____ DOLLARS CENTS			
501	10	EA	REMOVE AND RELOCATE EXISTING SIGNS FOR: _____ DOLLARS CENTS			
639.2X00NC	1	LS	CPM (CRITICAL PATH METHOD) SCHEDULE WITH MONTHLY UPDATE FOR: _____ DOLLARS CENTS			
645.5101	45	SF	GROUND-MOUNTED SIGN PANELS WITHOUT Z-BARS FOR: _____ DOLLARS CENTS			

**PROJECT NO. T62801-01  
 QUAKER MEETING HOUSE ROUNDABOUT  
 ITEMIZED PROPOSAL  
 FEBRUARY 2024**

Nassau County DPW

73 of 354

Contract no. T62801-01G  
 Quaker Meeting House Road Roundabout Construction

ITEM No.	APPROXIMATE VALUES					
	QUANTITY	UNIT				
645.5102	325	SF	GROUND-MOUNTED SIGN PANELS LESS THAN OR EQUAL TO 32 SF WITH Z-BARS FOR: _____ DOLLARS CENTS			
645.5103	295	SF	GROUND-MOUNTED SIGN PANELS GREATER THAN 32 SF WITH Z-BARS FOR: _____ DOLLARS CENTS			
645.81	68	EA	TYPE A SIGN POSTS FOR: _____ DOLLARS CENTS			
645.830203	6	EA	TYPE B SIGN POSTS FOR: _____ DOLLARS CENTS			
762 -7	6,500	SF	7 INCH THICK COLOR AND IMPRINTED PORTLAND CEMENT CONCRETE SIDEWALK FOR: _____ DOLLARS CENTS			
762-9	4,850	SF	9 INCH THICK COLOR AND IMPRINTED PORTLAND CEMENT CONCRETE SIDEWALK FOR: _____ DOLLARS CENTS			

**\* The unit price shown in the Itemized Proposal will be considered the unit price bid, although actual payment will be calculated based on changes in posted material prices.**